

6 070462

API NUMBER 15-051-02256-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW-SE-NW, SEC. 10, T 11 S, R 19 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245  
Operator: Okmar Oil Company  
Name & Address: 970 Fourth Financial Ctr.  
Wichita, Kans. 67202  
Robert Beren

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line  
Loose Name Falconberry Well # F-1  
County Ellis 117.55  
Well Total Depth 3617 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 227

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B.J. Titan License Number \_\_\_\_\_

Address Hays, Kansas, 67601

Company to plug at: Hour: 10:00 AM Day: 14<sup>th</sup> Month: March Year: 19 86

Plugging proposal received from Fred Crawford

(company name) Okmar Oil Company (phone) 316-265-7311

were: 8 5/8" - 227 FT SP. CUM 1/200<sup>SH</sup> cmt / 5 1/2" 3614 FT 1/125<sup>SH</sup> cmt.

Top of Cement 3004 FT, Squeezed @ 900 FT 1/40<sup>SH</sup> cmt

Refs: 3334-38, also open hole 3 1/2", Fred said 5 1/2" csg. 1805 FT

Order Proposal - 275<sup>SH</sup> Econolite, 6 3/5 Formix 10% Gel, 1/4<sup>th</sup> lb. cells, 2% Econolite

5<sup>SH</sup> shells, 7 1/2" Plug, approx 140 Pbs Water, Spot With, tubing

Plugging Proposal Received by Marion Schmidt (TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:00 PM Day: 14<sup>th</sup> Month: March Year: 19 86

ACTUAL PLUGGING REPORT Ordered 275<sup>SH</sup> Econolite, 6 3/5 Formix 10% Gel, 1/4 lb.

1/2 Cele-per stand 2% Econolite,

Ran tubing to 3625 FT Spotted 45<sup>SH</sup> cmt 1/2 shells.

Tubing @ 2521 FT Spotted 45<sup>SH</sup> cmt 1/2 shells.

Tubing @ 1440 FT Spotted 45<sup>SH</sup> cmt - Partial Circulated.

Tubing @ 396 FT Circulated 1/5<sup>SH</sup> cmt; Circulated Good Cement

Remarks: Squeezed Annulus 1/15<sup>SH</sup> cmt May Pressure 600<sup>PSIG</sup> - Shut In 425<sup>PSIG</sup>

(If additional description is necessary, use BACK of this form.)

Cemented By B.J. Titan

IN (V) (D) (E) observe this plugging.

DATE MAR 25 1986

INV. NO. 13140

Signed Marion Schmidt (TECHNICIAN) BOIC

3-14 MAY 08 1986

FORM CP-2/3 Rev. 01-84

RECEIVED STATE CORPORATION COMMISSION

MAR 21 1986 03-24-86

CONSERVATION DIVISION WICHITA, KANSAS

33 3-21-86