

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05084-00-00
Spot: NESESE Sec/Twnshp/Rge: 9-11S-19W
2970 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: GUSTUS Well Number: 3
County: ELLIS Total Vertical Depth: 3593 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: \$116.77
Surface Casing: Size 8.625 feet: 185 140 SX CMT
Production: Size 5.5 feet: 3590 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/28/2002 11:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perfs 3234' - 3273' - 3589'.
Casing parted at 1315'.
Lock set at 3200'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/28/2002 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Berexco RIH with tubing to 1298'. Pumped 40 sxs 60/40 pozmix, followed with 110 sxs cement and 500# hulls.
Cement circulated to surface.
Pulled tubing and tied onto casing with swedge and pumped 40 sxs cement with 100# hulls to circulate cement out backside.
Pumped an additional 40 sxs cement to pressure with Max. P.S.I. 450#.
S.I.P. 150#. Job complete.

RECEIVED
SEP 05 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #11717.

Plugged through: TBG

District: 04

Signed *Pat Staab*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-6-02

INV. NO. 2003060478

SEP 03 2002

WIA AD
DVIS
STAS

IWA OICED

OKMAR OIL

#3

GUSTUS

9-11-19W
NE SE SE

Contr. W L HARTMAN

ELLIS County

E 2054RB Comm.

Comp. 4-22-55

IP 74 BOPD

PHY POT

| Tops | Depth | Datum |
|------|-------|-------|
| TOP | 3012 | -958 |
| HEEB | 3234 | -1180 |
| KC | 3273 | -1219 |
| ARB | 3589 | -1535 |
| TD | 3593 | -1539 |

Casing
5" 3590

DD 3593: ACID 500: 12 BOPH

SOLOMON POOL

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS