

4-061177

1-26

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,995-0000

W2 SW /4 SEC. 09, 11 S, 19 W
1310 feet from S section line
4600 feet from E section line

Operator license# 30606

Lease: TWH Well # 1-9

Operator: Murfin Drilling Co., Inc.

County: Ellis 120.25

Address: 250 N. Water - Suite #300
Wichita, Kansas 67202

Well total depth 3700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 2:15 A.M. Day: 26 Month: January Year: 1999

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company Phone: 316-267-3241

Were: Order 215 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 7:00 A.M., Day: 26, Month: January, Year: 1999

Actual plugging report:

- 1st. Plug at 3619' w/25 sxs. - Arbuckle top 3644'.
- 2nd. Plug at 1450' w/25 sxs. - Anhydrite 1423' - 1463'.
- 3rd. Plug at 800' w/100 sxs. - Dakota 474' - 774'.
- 4th. Plug at 310' w/40 sxs. - Surface pipe 258'.
- 5th. Plug 40' w/10 sxs.
- Rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1999

Remarks: Allied Cementing.

CONSERVATION DIVISION
Wichita, Kansas

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2085 GL

I did [] / did not [X] observe the plugging.

(Signature)
(agent)
DK Form CP-2/3

INVOICED

DATE 3-1-99

INV. NO. 60664