

6-100526

TO:

11-1

API number 15- 051-24,942-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, ROOM #2078  
WICHITA, KANSAS 67202-3802

NE SW NW /4 SEC: 09 - 11 - 19 W  
1800 Feet from N (N/S) Line  
950 Feet from W (E/W) Line

Operator License# 05663

LEASE: Hall WELL # 1

Operator: Hess Oil Company

County: ELLIS 119-14

Address: P.O. Box 1009  
McPherson, KS 67460

Well total Depth 3666 feet  
Conductor Pipe inch @ feet  
Surface pipe 8 5/8 inch @ 261 feet

Aband. Oil Well Gas Well Input Well SWD: D and A: X

Plugging contractor: ShieldsDrilling Company License#: 05184

Address: Russell, KS

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Burt Berry

Company: Shields Phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs

1 st plug @ 3647 feet with 25 sacks	Rat hole: 15 sacks
2nd plug @ 1440 feet with 25 sacks	Mouse hole: 10 sacks
3rd plug @ 750 feet with 100 sacks	Wiper plug @ 40 foot
4th plug @ 300 feet with 40 sacks	
5th plug @ 40 feet with 10 sacks	

RECEIVED  
KANSAS CORP COMM  
NOV 15 12:01

Plugging proposal recived by: David Wann

Pluggings operations attended by agent? All [ ], Part [ ], None [ X ]

Completed Hour: 7:15 A Day: 1 Month: November Year: 1996

Actual plugging report Hole reported plugged as above.

Order 225 sx 60/40 Posmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2103 GL, Anhydrite top: 1440 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in place: Y

Plugged through drill pipe: Y

Arbuckle top: 3647 Cemented by: Allied Cementing

I did [ ] did NOT [ X ] observe the plugging.

David Wann P.I.R.T. III  
(agent)

INVOICED

DATE NOV 19 1996

INV. NO. 46993