

To: 6 031303
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-2
API NUMBER 15- 109-20,480-0000
SE SW SW, SEC. 4, T 11 S, R 38 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 06113
Operator: Landmark Oil Exp Inc.
Name & Address: 250 N. Water Suite 308
Wichita, Ks. 67202

330 feet from S section line
4290 feet from E section line
Lease Name Nollette Well # 1-4
County Logan 153.73
Well Total Depth 4730 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A
Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. License Number 5883
Address Wichita, Ks.

Company to plug at: Hour: PM Day: 2 Month: Dec Year: 19 89

Plugging proposal received from Burris
(company name) Warrior (phone) _____

were: 8 5/8" set at 359' w/250 sks cwc. Cir. hole w/no less than 36 vis
mud and with no loss or gain of fluid. Balance plugs w/mud. Order 200 sks 60/40 poz
6% gel 3% cal cl 8 5/8" wiper plug. Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:30PM Day: 2 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Spot plugs with drill pipe at 2625' w/25 sks

1800' w/100 sks and hulls
400' w/40 sks
40' w/10 sks and wiper plug
Circ 15 sks in rathole
Circ 10 sks in mousehole

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Anhy 2616 - 42 Elev. 3123'.
(If additional description is necessary, use BACK of this form.)

I (operator) will not observe this plugging.

INVOICED

DATE JAN 24 1990

INV. NO. 27128

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow