

To: 1 071073  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-22 API NUMBER 15- 135-23,685 0000 1460  
App. 150' W of  
S/2 NW SW, SEC. 4, T. 18 S, R. 24 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Operator: Abercrombie Drilling, Inc.  
Name & Address 150 N. Main, Suite 801  
Wichita, KS 67202

1650 feet from S section line

4770 feet from E section line

Lease Name Jones Estate Well # 1

County Ness

Well Total Depth 4385 142.51 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202-1383

Company to plug at: Hour: 11:15 a.m. Day: 22 Month: 6 Year: 19 92

Plugging proposal received from Tony Martin

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1613-47'

1st plug at 1650' with 50 sx cement, 2nd plug at 925' with 80 sx cement,

3rd plug at 460' with 40 sx cement, 4th plug at 260' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

\_\_\_\_\_

\_\_\_\_\_ Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 22 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement,

2nd plug at 925' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

(old / xxxxxx) observe this plugging.

DATE 7-16-92

INV. NO. 38673

Signed Dan Gordon  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 25 1992

CONSERVATION DIVISION  
Wichita, Kansas

FOR KCC USE:  
 EFFECTIVE DATE: 6-13-92  
 DISTRICT: 1  
 SSA: 1 No

State of Kansas  
 NOTICE OF INTENTION TO DRILL 135-23,685-0000  
 Must be approved by the K.C.C. five (5) days prior to commencing well  
 Spot Approx. 150' W East  
 S/2 - NW - SW ... Sec 4 ... Twp 18. S. Rg 24. X West

Expected Spud Date 6 month 8 day 92 year  
 OPERATOR: License # 5422  
 Name: Abercrombie Drilling, Inc.  
 Address: 150 N. Main, Suite 801  
 City/State/Zip: Wichita, KS 67202  
 Contact Person: Jack L. Partridge  
 Phone: 316-262-1841

CONTRACTOR: License #: 30684  
 Name: Abercrombie RTD, Inc.

Well Drilled For: Well Class: Type Equipment:  
 Oil  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 DWVD  Disposal  Wildcat  Cable  
 Seismic;  # of Holes  Other  
 If DWVD: old well information as follows:  
 Operator: N/A  
 Well Name: \_\_\_\_\_  
 Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore?  yes  no  
 If yes, true vertical depth: N/A  
 Bottom Hole Location: \_\_\_\_\_  
 Exp. 12/8/92

1650' FSL feet from South / North line of Section  
 4770' FEL feet from East / West line of Section  
 IS SECTION  REGULAR  IRREGULAR?  
 (NOTE: Locate well on the Section Plat on Reverse Side)  
 County: Ness  
 Lease Name: Jones Estate Well #: #1  
 Field Name: unknown  
 Is this a Prorated/Spaced Field?  yes  no  
 Target Formation(s): Fort Scott, Cherokee, Miss  
 Nearest lease or unit boundary: 510'  
 Ground Surface Elevation: unknown feet MSL  
 Water well within one-quarter mile:  yes  no  
 Public water supply well within one mile:  yes  no  
 Depth to bottom of fresh water: 400'  
 Depth to bottom of usable water: 700' 900'  
 Surface Pipe by Alternate: 1 250'  
 Length of Surface Pipe Planned to be set: \_\_\_\_\_  
 Length of Conductor pipe required: none  
 Projected Total Depth: 4450'  
 Formation at Total Depth: Miss.  
 Water Source for Drilling Operations:  
 well  farm pond  other  
 DWR Permit #: will file  
 Will Cores Be Taken?:  yes  no  
 If yes, proposed zone: N/A

200' Alt. II Req. AFFIDAVIT

I, the undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Tony Martin  
 SPUD DATE 6-15-92 INIT. DG  
 LENGTH SURFACE PLANNED 250'  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. \_\_\_\_\_ bbls. when done \_\_\_\_\_ bbls.  
 RATHOLED AHEAD?  Y  N SIZE HOLE \_\_\_\_\_  
 SURFACE PIPE 8 3/4" @ 253' CONDUCTOR \_\_\_\_\_  
 ANHYDRITE T- 1613 B- 1641 ELEVATION \_\_\_\_\_  
 TD 4385 FORMATION \_\_\_\_\_  
 RAN PIPE @ \_\_\_\_\_ DV TOOL ALT II DONE  
 \_\_\_\_\_ SX \_\_\_\_\_ SX Y \_\_\_\_\_ N \_\_\_\_\_  
 Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 Anhydrite Base @ 1650 Ft. W/ 30 SX  
 1/2 Base Anyh. @ 925 Ft. W/ 80 SX  
 1/2, 1/2 Plug @ 460 Ft. W/ 40 SX  
 Bottom Surface @ 260 Ft. W/ 50 SX  
 40' Plug @ 40 Ft. W/ 10 SX  
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
 WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
 \_\_\_\_\_ Hauling \_\_\_\_\_  
 TECHNICIAN S.M. DATE 6-22-92  
 TYPE OF CEMENT \_\_\_\_\_  
 STARTING TIME 6:00 (AM/PM) DATE \_\_\_\_\_  
 COMPLETION TIME 2:55 (AM/PM) DATE \_\_\_\_\_  
 CEMENT \_\_\_\_\_ (AM/PM) DATE \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 25 1992  
 CONSERVATION DIVISION  
 Wichita, Kansas