

1 090150

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-16 99
API NUMBER 15- 135-23,635-0000
Approx. 150'
SW SE NE, SEC. 4, T 18 S, R 24 WXB

3165 feet from S section line
795 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Potter Well # 3

Operator: Viking Resources, Inc.
Name & Address: 105 S. Broadway, Suite 1040
Wichita, KS 67202

County Ness 141.53

Well Total Depth 4355 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mallard JV, Inc. License Number 4958

Address P.O. Box 1009, McPherson, KS 67460

Company to plug at: Hour: 12:30 p.m. Day: 16 Month: 12 Year: 19 91

Plugging proposal received from Julie

(company name) Mallard JV, Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1616-46'
1st plug at 1660' with 50 sx cement, 2nd plug at 900' with 80 sx cement,
3rd plug at 400' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 16 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1660' with 50 sx cement,
2nd plug at 900' with 80 sx cement,
3rd plug at 400' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE 1-7-92

Wichita, Kansas Signed _____

(TECHNICIAN)

INV. NO. 34234
12-16

CONSERVATION DIVISION
WICHITA, KANSAS

EXPECTED DATE: 12-11-91

NOTICE OF INTENTION TO DRILL 135-23,635-0000 ALL BLANKS MUST BE FILLED

Must be approved by the K.E.C. five (5) days prior to commencing well

Expected Spud Date: 12 month 11 day 1991 year

Approved: SW - SE - NE Sec 4 - Twp 18 S - Rg 24 E

OPERATOR: License # 5011
Name: Viking Resources, Inc.
Address: 105 S. Broadway, Suite 1040
City/State/Zip: Wichita, KS 67202
Contact Person: James B. Devlin
Phone: 316-262-2502

3165 feet from South / North line of Section
795 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse side)

County: Ness
Lease Name: Potter Well # 3
Field Name: Unknown

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Miss
Nearest lease or unit boundary: 795

Ground Surface Elevation: 2320 est feet HSL
Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 100

Depth to bottom of usable water: 1000
Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 250
Length of Conductor pipe required: none

Projected Total Depth: 4400
Formation at Total Depth: Miss

Water Source for Drilling Operations:
well X farm pond other

BLR Permit #:
Will cores be taken? yes X no

If yes, proposed zone:
200' Alt. II Req.

CONTRACTOR: License #: 4958
Name: Mallard JV, Inc.

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWO Disposal Mildest Cable
Seismic # of Holes Other

If OWO, old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 6/6/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Jolie SPUD DATE 12-10-91 INIT. RL

LENGTH SURFACE PLANNED 250'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 263 CONDUCTOR
ANHYDRITE T- 1616 B- 46 ELEVATION
Safety at

TD FORMATION

RAN PIPE @ DV TOOL ALT II DONE
 SX SX Y N

 Arbuckle Plug @ Ft. W/ SX
 Hug./Council @ Ft. W/ SX
 Anhydrite Base @ 1660 Ft. W/ 50 SX
 1/2 Base Anyh. @ 900 Ft. W/ 80 SX
 1/2, 1/2 Plug @ Ft. W/ SX
 Bottom Surface @ 410 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond)
Hauling

TECHNICIAN JOR DATE

TYPE OF CEMENT 60-10-670 4 phases

STARTING TIME : (AM/PM) DATE

COMPLETION TIME : (AM/PM) DATE

CEMENT COMPANY