

1 080322

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,769 - ~~0000~~ *R*

S/2 SE SW, SEC. 9, T 18 S, R 24 W/X

330 feet from S section line

3250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Wells "E" Well # 1

Operator: TXO Production Corp.

County Ness 144.63

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 4450 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 8 Month: February Year: 19 85

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-265-9441

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1600' with 50 sx cement

2nd plug at 800' with 40 sx cement

3rd plug at 380' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 6:15 am Day: 8 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1600' with 50 sx cement, 2nd plug at 800' with 40

sx cement, 3rd plug at 380' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 15 1985  
2-15-85  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

DATE I  (Kkd / did not) observe this plugging.

INV. NO. 7101

Signed *J. H. Metz* (TECHNICIAN)

2-8

MAR 15 1985

OPERATOR MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 1 31 85  
month day year

API Number is- 135-22769-09885  
*Plugged @ 6:15am*

S/2 SE SW Sec 9 Twp 18 S, Rge 24  
(location)  East  West

OPERATOR: License # 5171  
Name TXO Production Corp.  
Address 200 W. Douglas, Suite 300  
City State/Zip Wichita, KS 67202  
Contact Person Gary Wurdeman  
Phone 316-265-9441

3250' 330 Ft North from Southeast Corner of Section  
3300 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033  
Name Murfin Drilling Company  
City State Wichita, KS

Nearest lease or unit boundary line 330 feet.

County Ness

Lease Name WELLS "E" Well# 1

Domestic well within 330 feet:  yes  no

Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Est.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 100 feet

Lowest usable water formation Cheyenne

Depth to Bottom of usable water 775 feet

Surface pipe by Alternate: 1  2

Surface pipe to be set 335 feet

Conductor pipe if any required 0 feet

Ground surface elevation TBD feet MSL

This Authorization Expires 7-23-85

Approved By 1-23-85

OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4450 feet  
Projected Formation at TD Miss  
Projected Producing Formations Miss

1-23-85 Signature of Operator or Agent

*Jerry W. Collins* Title Drilling & Completion Engr.  
MHC/WOHE 1-23-85 Form C-1 4/84

135-85/8 2-1-85

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1985

CONSERVATION DIVISION  
Wichita, Kansas