

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02961-00-00  
Spot: NENENW Sec/Twnshp/Rge: 2-14S-17W  
4982 feet from S Section Line, 3022 feet from E Section Line  
Lease Name: BRAUN B Well #: 2  
County: ELLIS Total Vertical Depth: 3469 feet

Operator License No.: 34248  
Op Name: ALBERT R. BRAUN OIL OPERATIONS.  
Address: 2701 E. 17TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3461		150 SX
SURF	8.625	900		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/20/2012 8:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: ALBERT R. BRAUN Company: BRAUN OIL OPERATIONS LLC Phone: (785) 623-4574

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 12 sx gel and 600 # hulls.  
Perforated: Lans - 3216' and ARB - 3460'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/20/2012 1:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Lk wire line perforated @ 1600', 1125' and 450'.  
Express Well Service ran in hole with tubing to 3299'. Quality rigged to tubing, mixed and pumped 12 sx gel followed by 50 sx cement w/250 # hulls.  
Pulled tubing to 1600'. Quality rigged to tubing, mixed and pumped 190 sx w/200 # hulls to circulate cement up 5 1/2" casing.  
Pulled tubing. Rigged to 5 1/2" with a swedge and pumped 105 sx to circulate cement out 8 5/8" casing. Shut in casing. Pumped 5 sx cement to pressure up 5 1/2" and 8 5/8" casing with 200 psi. Shut in pressure 200 psi.

RECEIVED  
AUG 27 2012  
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING CO TICKET # 786

Plugged through: TBG

District: 04

Signed

  
8/20/12 (TECHNICIAN)

CM

AUG 21 2012