

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03104-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 11-14S-20W  
feet from Section Line, feet from Section Line  
Lease Name: BEFORT Well #: 4  
County: ELLIS Total Vertical Depth: 3842 feet

Operator License No.: 4871  
Op Name: CURT-S OIL OPERATIONS LLC  
Address: PO 8  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3837		125 sx
SURF	8.625	238		140 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/15/2012 3:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMAN Company: CURTIS OIL OPERATIONS Phone: (620) 653-7330

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls  
DV tool @ 1482.64' w/500 sx.  
PBTB - 3841'.  
Junk in hole @ 2096'.  
Emergency Plug with Rig over Hole.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/15/2012 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

DS&W ran in hole with tubing to 2076'. Allied rigged to tubing, mixed and pumped 100 sx cement w/250 # hulls.  
Pulled tubing to 700'. Pumped 60 sx cement w/250 # hulls to circulate cement to surface.  
Pulled tubing, rigged to 4 1/2" casing with a swedge and pumped 5 sx cement to pressure with 350 psi. Shut in pressure 350 psi.  
Rigged to 8 5/8" casing. Instant pressure @ 1000 psi.  
Operator washed over pipe.  
Operator also ran a bit and milled on pipe. Could not get on rods.


RECEIVED  
AUG 27 2012  
KCC WICHITA

Remarks: ALLIED CEMENTING CO TICKET # 56304

Plugged through: TBG

District: 04

Signed

  
8/31/12

(TECHNICIAN)

CM

AUG 20 2012