

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23838-00-00
Spot: SWSWSESW Sec/Twnshp/Rge: 28-10S-25W
230 feet from S Section Line, 1615 feet from W Section Line
Lease Name: KNOLL Well #: 1-28
County: GRAHAM Total Vertical Depth: 4300 feet

Operator License No.: 34440
Op Name: ENERGY INVESTMENT PARTNERS, LL

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	252		185 sx

Address: PO BOX 225878
DALLAS, TX 75222

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/04/2012 12:00 AM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: JEREMY Company: MAVERICK DRILLING LLC Phone: (620) 388-6419

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE
Date/Time Plugging Completed: 08/04/2012 12:30 PM

WitnessType: NONE
KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

1st plug @2150 w/25 sx
2nd plug @1425 w/100 sx
3rd plug @300 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: SOS

Plugged through: DP

RECEIVED
AUG 27 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
8/30/12 (TECHNICIAN)

CM

AUG 22 2012