

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-125-02256-00-00  
Spot: NENESENW Sec/Twnshp/Rge: 7-34S-14E  
3799 feet from S Section Line, 2866 feet from E Section Line  
Lease Name: BURRIS Well #: B-29  
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 34458  
Op Name: LONG AND WARE OIL, A GENERAL PA  
Address: PO BOX 554  
WYNONA, OK 74081

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	700		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2012 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN LONG Company: \_\_\_\_\_ Phone: (918) 698-8080

Proposed Plugging Method: Run 1" to bottom, gel hole, spot 20 sacks of cement, pull 1" out, perforate casing at 250', run 1" in, cement 250' to surface inside and outside of casing, pull 1" out, top off with cement, cut well head off below surface, restore location.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed 06/11/2012 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 700' gelled hole and spotted 15 sack plug. Pulled 1" and perforated casing at 225'.  
Ran 1" back into 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 91 sacks of cement were used to plug this well.

RECEIVED

AUG 1 2012

KCC Chanute Dist. #3

DAS

RECEIVED  
AUG 17 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

*[Signature]*  
8/28/12

(TECHNICIAN)