

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02446-00-01
Spot: SENENE Sec/Twnshp/Rge: 26-14S-13W
4299 feet from S Section Line, 457 feet from E Section Line
Lease Name: RAY SHAFFER Well #: 3
County: RUSSELL Total Vertical Depth: 3257 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3251		250 SX
PKR		3168		
PROD	5.5	2359		75 SX
SURF	8.625	203		135 SX

Well Type: SWD UIC Docket No: D16775.0 Date/Time to Plug: 08/08/2012 9:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DON BROWNING Company: YOUNGER ENERGY CO Phone: (785) 810-8230

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls and 8 sx gel.
Perfs: 325', 650', and 1220'.
Old packer in the bottom of well @ 3160'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2012 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs: .

Ran tubing to 3140'. Pumped 8 sx gel followed by 75 sx cement w/100 # hulls.
Pulled tubing to 1250'. Pumped 125 sx cement w/200 # hulls.
POOH. Hooked on to casing and pumped 20 sx cement @ 1000 psi. Shut in pressure 700 psi.
Braden head was full of cement from squeeze job on 05/16/2012.

RECEIVED
AUG 17 2012
KCC WICHITA

Remarks: ALLIED CEMENTING TICKET # 56474

Plugged through: TBG

District: 04

Signed

R. A. D. KED

(TECHNICIAN)

CM

AUG 10 2012

cc to UIC
8/21/22

8/28/12