

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22798-00-00
Spot: NENESESW Sec/Twnshp/Rge: 27-13S-22W
1010 feet from S Section Line, 2550 feet from W Section Line
Lease Name: MONG BENNO Well #: 2
County: TREGO Total Vertical Depth: 4285 feet

Operator License No.: 6037
Op Name: STAAB OIL CO., A GENERAL PARTNER
Address: 1607 HOPEWELL RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2012 12:00 AM
Plug Co. License No.: 5655 Plug Co. Name: SHIELDS DRILLING CO., INC.
Proposal Rcvd. from: TOM ENGEL Company: SHIELDS DRILLING CO., INC. Phone: (785) 483-3141

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 08/07/2012 6:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1825 w/25 sx
2nd plug @900 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

RECEIVED
AUG 17 2012
KCC WICHITA

Remarks: QUALITY CEMENTING

Plugged through: DP

District: 04

Signed

CASE MORRIS
8/28/12 (TECHNICIAN)

AUG 10 2012