

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20408-00-00
Spot: NENWSE Sec/Twnshp/Rge: 30-25S-4E
2338 feet from S Section Line, 1636 feet from E Section Line
Lease Name: OSBURN Well #: 2
County: BUTLER Total Vertical Depth: 2640 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2637		50 SX
SURF	8.625	202		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2012 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVEN W. KILE Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/26/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2630', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2160. TESTED CASING @ 100#, HELD OK. RIH ON WIRELINE, CUT CASING @ 550', LAYED DOWN 17 JOINTS 5.5" CASING (550"). RIH W/TBG @ 250', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 93 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-26-2012. CONSOLIDATED CEMENT TICKET #34795.

Perfs:

Top	Bot	Thru	Comments
2637	2640	OH	OHIO

RECEIVED
AUG 17 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
8/28/12 (TECHNICIAN)

✓JK