

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-25054-00-00
Spot: SENESWNE Sec/Twnshp/Rge: 10-34S-10E
3460 feet from S Section Line, 1480 feet from E Section Line
Lease Name: ROBINSON Well #: 2-A
County: CHAUTAUQUA Total Vertical Depth: 1515 feet

Operator License No.: 33594
Op Name: QUITO, INC.
Address: 1613 W 6TH ST
BARTLESVILLE, OK 74003

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1515		110 SX
SURF	7	41		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/29/2012 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: DEAN MCCANN Company: _____ Phone: (620) 249-4898

Proposed Plugging Method: Filling casing with cement as instructed by District 3 office.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 03/16/2012 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1600' gelled hole and spotted 10 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled 1" and perforated casing at 550' . Ran 1" back into 550' and circulated cement to surface. Pulled 1" and spueezed casing. Cement was squeezed to surface on backside of casing. A total of 85 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1474	1484		

RECEIVED
AUG 17 2012
KCC WICHITA

RECEIVED
AUG 1 2012 DAS
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
8/28/12 (TECHNICIAN)