

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10058-00-00
Spot: SW Sec/Twnshp/Rge: 2-32S-42W
2640 feet from S Section Line, 3960 feet from E Section Line
Lease Name: LUNT Well #: 1-2
County: MORTON Total Vertical Depth: 3375 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3214	651	WITH 400 SX CMT
SURF	8.625	615		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/09/2012 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUG AT 1800' WITH 60 SX CMT. PULL STRETCH. CIRCULATE WITH MUD. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 08/13/2012 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 1720' WITH 60 SX CMT. TAG TOC @ 1344'. (TBG STUCK IN HOLE. CUT TBG OFF @ 1750') 2ND PLUG AT 651' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3029	3170		
2804	3012		

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

RECEIVED
AUG 20 2012
KCC WICHITA

District: 01

Signed

Ken Jehlik
8/28/12

(TECHNICIAN)

RECEIVED
AUG 16 2012
KCC DODGE CITY

RAW