

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20684-00-01
Spot: SWNESENW Sec/Twnshp/Rge: 13-21S-35W
1974 feet from N Section Line, 1981 feet from W Section Line
Lease Name: SCOTT Well #: 1-13
County: KEARNY Total Vertical Depth: 4511 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY DR STE350
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1100		
CIBP		2670		
DVT		2016		WITH 475 SX CMT
PROD 5.5		4418	0	WITH 275 SX CMT
SURF 8.625		564		WITH 250 SX CMT

Well Type: WSW UIC Docket No: Date/Time to Plug: 08/10/2012 8:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GORDON AUSTIN Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2012 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2670'. SPOT 80 SX CMT AT 2118' THROUGH TBG. PARTIAL RETURNS. SET CIBP @ 1100' WHICH IS ABOVE CASING LEAK. RUN TBG TO 977' & CIRCULATE CMT TO SURFACE WITH 110 SX CMT. TOOH W/TBG & TOP OFF 5 1/2" WITH 10 SX CMT. PUMP 50 SX CMT DOWN ANNULUS TO 100#. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3600	4144		
RECEIVED AUG 20 2012			

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

KCC WICHITA

District: 01

RECEIVED

AUG 16 2012

KCC DODGE CITY

Signed

(TECHNICIAN)