

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20711-00-02  
Spot: SWNW Sec/Twnshp/Rge: 4-35S-41W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WILBURTON MORROW SAND Well #: 2105  
County: MORTON Total Vertical Depth: 5050 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4790		
COND	20	20		
PROD	5.5	5044	1517	WITH 125 SX CMT
SURF	8.625	1490		WITH 800 SX CMT

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2012 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUG OFF BOTTOM WITH HULLS & 25 SX CMT TO 3150'. PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/15/2012 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 1000# HULLS & 50 SX CMT IN 2 STAGES. TAGGED TOC IN 5 1/2" CASING @ 3015'. 1ST PLUG AT 1503' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4901	4909		
4855	4886		
3439	3472		
3425	3435		
3392	3420		
3271	3295		
3252	3266		
3195	3210		

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

RECEIVED  
AUG 20 2012

KCC WICHITA

District: 01

Signed Ken Jehlik  
8/28/12 (TECHNICIAN)

RECEIVED  
AUG 16 2012  
KCC DODGE CITY