

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-001-22002-00-01 ;  
Spot: NWSWNE Sec/Twnshp/Rge: 21-26S-21E  
3700 feet from S Section Line, 2450 feet from E Section Line  
Lease Name: H A WILLIAMS Well #: W 10  
County: ALLEN Total Vertical Depth: 733 feet

Operator License No.: 34078  
Op Name: NEWMAN, BRENT L. DBA B & S OIL  
Address: 4290 NEBRASKA RD  
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	735		90 sx
SURF	6.25	21		3 sx

Well Type: EOR UIC Docket No: E29045.10 Date/Time to Plug: 03/09/2012 8:00 AM  
Plug Co. License No.: 31813 Plug Co. Name: BECKER, STEVE A. DBA A & A WELL SERVICE  
Proposal Rcvd. from: A&A WELL SERVICE Company: Phone: (620) 363-4124

Proposed Plugging Method: RUN 1" IN TO BOTTOM, PUMP 5 SACKS CEMENT. PULL 250' 1" OUT AND PUM[ 5 MORE SACKS, STAGE AGAIN 2 MORE TIMES AND TOP WELL WITH CEMENT. COMPLETE WELL PLUGGING METHOD WITH 23 SACKS.

Plugging Proposal Received By: WitnessType: PARTIAL  
Date/Time Plugging Completed 03/09/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2 1/2" casing to 733'. Circulated cement through the 1" pipe inside the 2 1/2" casing at TD. Pulled 250' of 1" pipe. Circulated cement through the 1" pipe inside the 2 1/2" casing at 500'. Pulled 250' of 1" pipe. Circulated cement through the 1" pipe and cemented from 250' to surface. Pulled the rest of the 1" pipe and topped the well off with cement. A total of 23 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
654	692		

RECEIVED

AUG 17 2012 RMD

KCC Chanute Dist. #3

RECEIVED  
AUG 22 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

*[Signature]*  
(TECHNICIAN)  
cc to JMC 8/28/12