

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-22003-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 21-26S-21E
3500 feet from S Section Line, 2225 feet from E Section Line
Lease Name: H A WILLIAMS Well #: W 11
County: ALLEN Total Vertical Depth: 738 feet

Operator License No.: 34078
Op Name: NEWMAN, BRENT L. DBA B & S OIL
Address: 4290 NEBRASKA RD
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	739		90 sx
SURF	6.25	21		3 sx

Well Type: EOR 1 UIC Docket No: E29045.11 Date/Time to Plug: 03/09/2012 8:00 AM
Plug Co. License No.: 31813 Plug Co. Name: BECKER, STEVE A. DBA A & A WELL SERVICE
Proposal Rcvd. from: A & A WELL SERVICE Company: Phone: (620) 363-4124

Proposed Plugging Method: RUN 1" IN TO BOTTOM, PUMP 5 SACKS CEMENT. PULL 250' 1" OUT AND PUMP 5 MORE SACKS, STAGE AGAIN 2 MORE TIMES AND TOP OFF WELL WITH CEMENT. COMPLETE WELL PLUGGING METHOD WITH 23 SACKS.

Plugging Proposal Received By: WitnessType: PARTIAL
Date/Time Plugging Completed 03/08/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2 1/2" casing to 738'. Circulated cement through the 1" pipe inside the 2 1/2" casing at TD. Pulled 250' of 1" pipe. Circulated cement through the 1" pipe inside the 2 1/2" casing at 500'. Pulled 250' of 1" pipe. Circulated cement through the 1" pipe and cemented from 250' to surface. Pulled the rest of the 1" pipe and topped the well off with cement. A total of 23 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
676	709		

RECEIVED
AUG 22 2012
KCC WICHITA

RECEIVED

AUG 17 2012

KCC Chanute Dist. #3

RMD

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)
cc to MIC 8/29/12
8/28/12