

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20857-00-00
Spot: E2NWNWNW Sec/Twnshp/Rge: 34-33S-19W
4955 feet from S Section Line, 4765 feet from E Section Line
Lease Name: LEWIS Well #: 1-34A
County: COMANCHE Total Vertical Depth: 6501 feet

Operator License No.: 30104
Op Name: CAMBRON, PAUL L.
Address: 118 N PENN PO BOX 384
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5580	3200	WITH 120 SX CMT
SURF	8.625	648		WITH 215 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/08/2012 2:30 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAL HOSS Company: PAUL CAMBRON Phone: (785) 798-5051

Proposed Plugging Method: CIBP @ 5200'. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 08/08/2012 8:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

COULDN'T GET THE CIBP PAST 3650'. RAN TBG TO 5200' & PUMPED 30 SX CMT WITH 200# HULLS. TOC @ 4190'. SHOT OFF CASING AT 3200'. 1ST PLUG AT 980' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 680' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5298	5312		
5218	5326		

RECEIVED
AUG 22 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Eric Maclaren
8/28/12 (TECHNICIAN)

RECEIVED
AUG 17 2012
KCC DODGE CITY

Handwritten initials