

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20443-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 8-33S-19W
2317 feet from S Section Line, 2309 feet from E Section Line
Lease Name: ZIELKE Well #: 6-8
County: COMANCHE Total Vertical Depth: 5325 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5110		
PROD	4.5	5311	2400	WITH 250 SX CMT
SURF	8.625	705		WITH 500 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/07/2012 1:30 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: BP AT 5110'. PLUG AT 950' WITH 15 SX GEL & 40 SX CMT. PLUG AT 740' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 30' WITH 10 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2012 2:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 5110'. 1ST PLUG AT 945' WITH 15 SX GEL & 40 SX CMT. 2ND PLUG AT 756' WITH 50 SX CMT. 3RD PLUG AT 252' WITH 40 SX CMT. 4TH PLUG AT 58' WITH 45 SX CMT. 8/14/12: TOPPED OFF WITH 1 1/4 YARDS OF READY MIX CEMENT.

Perfs:

Top	Bot	Thru	Comments
5153	5222		MISSISSIPPI

RECEIVED
AUG 22 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren
8/28/12 (TECHNICIAN)

RECEIVED
AUG 17 2012
KCC DODGE CITY