

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21027-00-02
Spot: NWSESWNE Sec/Twnshp/Rge: 4-32S-19W
2307 feet from N Section Line, 1657 feet from E Section Line
Lease Name: INEZ BEAN Well #: 1-4
County: COMANCHE Total Vertical Depth: 5370 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4540		WITH 2 SX CMT
CIBP		5063		WITH 2 SX CMT
COND	13.375	285		WITH 300 SX CMT
PROD	4.5	5370	2500	WITH 310 SX CMT
SURF	8.625	685		WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/10/2012 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 5070' WITH 2 SX CMT. CIBP @ 4540' WITH 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2012 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5063' WITH 2 SX CMT. SET CIBP @ 4540' WITH 2 SX CMT. 1ST PLUG AT 1102' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 693' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 50 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5310	5310		to shut off perfs 531
5290	5294		
5240	5320		
5122	5123		
4871	4872		
4595	5499		

RECEIVED
AUG 22 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Kenny Sullivan
8/27/12
(TECHNICIAN)

RECEIVED
AUG 14 2012
KCC DODGE CITY

RMM