

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21233-00-00
Spot: NENWNWNE Sec/Twnshp/Rge: 4-32S-19W
4960 feet from S Section Line, 2273 feet from E Section Line
Lease Name: INEZ BEAN Well #: 2-4
County: COMANCHE Total Vertical Depth: 5373 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4715		WITH 2 SX CMT
CIBP		5280		
COND	20	80		
	11 8.625	657		
PROD	4.5	5373	2700	WITH 250 SX CMT
SURF	13.375	298		WITH 210 SX CMT

Well Type: SWD UIC Docket No: D27908.0 Date/Time to Plug: 08/15/2012 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4700' WITH 2 SX CMT. PLUG AT 1100' IWHT 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2012 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4715'. PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1102' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 724' WITH 50 SX CMT. 3RD PLUG AT 315' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5298	5310		
4768	4774		

RECEIVED
AUG 22 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
AUG 17 2012
KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)
cc to WIC 8/23/12
8/27/12