

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21295-00-00
Spot: S2N2SEW Sec/Twnshp/Rge: 34-33S-28W
1780 feet from N Section Line, 1980 feet from W Section Line
Lease Name: WIENS Well #: 2-34
County: MEADE Total Vertical Depth: 5750 feet

Operator License No.: 33649
Op Name: KENNETH W. CORY, LTD.
Address: 6750 W. LOOP SOUTH, STE 1050
BELLAIRE, TX 77401

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5595		WITH 2 SX CMT
COND	20	80		WITH 25 SX CMT
PROD	5.5	5750	2185	WITH 260 SX CMT
SURF	8.625	1516		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/13/2012 9:30 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: MARY HORNEY Company: MIDWESTERN WELL SERVICE, IN Phone: (580) 334-8663

Proposed Plugging Method: SET CIBP @ 5600' WITH 2 SX CMT. PLUG AT 1540' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2012 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5595' WITH 2 SX CMT. 1ST PLUG AT 1540' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5648	5656		

RECEIVED
AUG 22 2012

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed: [Signature]
(TECHNICIAN)

RECEIVED

AUG 17 2012

KCC DODGE CITY

ROW