

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19031-00-01
Spot: SWSWESW Sec/Twnshp/Rge: 32-24S-13W
1639 feet from S Section Line, 1638 feet from W Section Line
Lease Name: BELOTE Well #: 3-32
County: STAFFORD Total Vertical Depth: 4237 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3700 | | WITH 2 SX CMT |
| CIBP | | 4070 | | WITH 2 SX CMT |
| PROD | 5.5 | 4232 | 1607 | WITH 275 SX CMT |
| SURF | 8.625 | 255 | | WITH 225 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2012 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEITH SHAHAN Company: CHESAPEAKE OPERATING Phone: (405) 935-4594

Proposed Plugging Method: SET CIBP @ 4200' & 2 SX CMT. SET CIBP @ 3700' & 2 SX CMT. PLUG AT 890' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. P LUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 08/15/2012 10:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4070' WITH 2 SX CMT ON TOP. SET CIBP @ 3700' WITH 2 SX CMT. 1ST PLUG AT 895' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 292' WITH 50 SX CMT. 3RD PLUG AT 90' WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4230 | 4237 | | |
| 3788 | 3970 | | |

RECEIVED
AUG 22 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
AUG 17 2012
KCC DODGE CITY

Signed Richard W. Lacey
8/28/12 (TECHNICIAN)

ROY