

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04343-00-01
Spot: SWSESWNW Sec/Twnshp/Rge: 4-18S-14W
2955 feet from S Section Line, 4493 feet from E Section Line
Lease Name: C FRIEB Well #: 2
County: BARTON Total Vertical Depth: 3478 feet

Operator License No.: 4323
Op Name: REICHLINGER, GARY DBA REICHLING
Address: 118 W 8TH ST PO BOX 4
YORK, NE 68467

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3152		
COND	13	245		150 SX
PROD	6	3472		250 SX
SURF	8.625	946		150 SX

Well Type: EOR UIC Docket No: E15841.1 Date/Time to Plug: 07/26/2012 9:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GARY REICHLINGER Company: REICHLINGER BUS Phone: (402) 362-4191

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/400 # hulls and 9 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforations @ 950'.
Ran tubing to 2900'. Pumped 9 sx gel followed by 60 sx cement w/100 # hulls.
Pulled tubing to 1500'. Pumped 100 sx cement w/200# hulls.
Pulled tubing to 500'. Pumped 50 sx cement. Circulated cement to surface on casing.
Pulled tubing. Topped off w/5 sx cement.

Perfs:

Top	Bot	Thru	Comments
3472	3478		ARBUCKLE
3404	3408		LKC-J
3233	3266		LKC-A

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)
RECEIVED

CM

JUL 27 2012

cc to MG 8/9/12
8/15/12

AUG 08 2012

Form CP-2/3

KCC WICHITA