

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20159-00-00
Spot: N2SWSNW Sec/Twnshp/Rge: 4-18S-14W
3045 feet from S Section Line, 3630 feet from E Section Line
Lease Name: C FRIEB B Well #: 8-D
County: BARTON Total Vertical Depth: 3444 feet

Operator License No.: 4323
Op Name: REICHLINGER, GARY DBA REICHLING
Address: 118 W 8TH ST PO BOX 4
YORK, NE 68467

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3013		
PROD	5.5	3444		175 SX
SURF	8.625	279		174 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2012 9:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GARY REICHLINGER Company: REICHLINGER BUS Phone: (402) 362-4191

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 400 # hulls and 9 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforations at 1450' and 950'.
Ran tubing to 2900'. Pumped 9 sx gel followed w/50 sx cement w/100 # hulls.
Pulled tubing to 1500'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 500'. Pumped 40 sx cement. Circulated cement to surface on casing.
Pulled tubing. Tied to casing. Pumped 5 sx cement. Pressured to 300 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
3444	3449		ARBUCKLE

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie
8/15/12

(TECHNICIAN) RECEIVED

CM

JUL 27 2012

AUG 08 2012

Form CP-2/3

KCC WICHITA