

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03783-00-00  
Spot: N2NENW Sec/Twnshp/Rge: 5-17S-11W  
4950 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: SCHNEWEIS Well #: 5  
County: BARTON Total Vertical Depth: 3338 feet

Operator License No.: 31086  
Op Name: RICHLAN DRILLING, A GENERAL PAR  
Address: 598 2ND AVE  
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	4.5	3325		175 SX
PROD	5.5	3330		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2012 2:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICK SCHREIBER Company: SCHREIBER OIL Phone: (620) 793-2032

Proposed Junk in well at 1200'.  
Plugging Ordered 500 sx 60/40 pozmix 4% gel cement.  
Method: Well has 4 1/2" liner ran to 3325' cemented w/125 sx cement. Cement circulated.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 700' and 250'.  
Ran tubing to 1200'. Tied to tubing and pumped 50 sx cement.  
Pulled tubing to 600'. Circulated cement to surface on casing w/60 sx cement.  
Pulled tubing. Tied to casing and pumped 60 sx cement. Fluid started coming out of ground 4' from well head.  
Pumped 45 sx cement and stopped pumping. Will dig out well head when area dries out and check well head in ground.

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED

8/15/12

AUG 08 2012

Form CP-2/3

AUG 02 2012

KCC WICHITA