

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23641-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 10-10S-18W
2771 feet from N Section Line, 2672 feet from W Section Line
Lease Name: ADDISON Well #: 10-1
County: ROOKS Total Vertical Depth: 3765 feet

Operator License No.: 9531
Op Name: WALLACE ENERGY, INC.
Address: 2690 17 RD
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3707		100 SX CMT.
SURF	8.625	220		150 SX CMT.
T1	2.875	3654		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2012 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: AVON WEAVERLING Company: WALLACE ENERGY INC. Phone: (785) 623-3221

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement.
DV tool @ 1530' w/350 sx
Hole full of drilling mud.
3 drill collars and 2 joints of tubing stuck in hole. TOT @ 3640'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2012 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3639'. Pumped 50 sx cement w/100 # hulls.
Pulled tubing to 1546'. Pumped 135 sx cement to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing w/10 sx cement.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 5 sx cement.

Perfs:

Top	Bot	Thru	Comments
3658	3662		

Remarks: QUALITY OILWELL CEMENTING TICKET # 811

Plugged through: TBG

District: 04

Signed

Pat Bedore
8/15/12
(TECHNICIAN)

CM

RECEIVED

AUG 08 2012

KCC WICHITA

Form CP-2/3

JUL 27 2012