

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20610-00-00
Spot: NESENESE Sec/Twnshp/Rge: 1-3S-21W
1738 feet from S Section Line, 150 feet from E Section Line
Lease Name: SCHEMPER-ROMJUE UNIT Well #: 1
County: NORTON Total Vertical Depth: 4048 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/31/2012 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGIE Company: WW DRILLING, LLC Phone: (785) 743-6724

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 07/31/2012 6:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

1st plug @2012 w/25 sx
2nd plug @1224 w/100 sx
3rd plug @301 w/40 sx
4th plug @40 w/10 sx


Rathole 30 sx

Remarks: ALLIED

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

8/15/12

AUG 08 2012

KCC WICHITA

AUG 02 2012