

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21579-00-00
Spot: NWSE Sec/Twnshp/Rge: 23-23S-24W
1746 feet from S Section Line, 1754 feet from E Section Line
Lease Name: POVERTY HILL Well #: 1
County: HODGEMAN Total Vertical Depth: 4761 feet

Operator License No.: 33856
Op Name: WHITE EXPLORATION, INC.
Address: 2400 N WOODLAWN STE 115
WICHITA, KS 67220

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4622		WITH 2 SX CMT
DVT		1599		WITH 360 SX CMT
PROD	5.5	4758	0	WITH 200 SX CMT
SURF	8.625	234		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2012 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: SET CIBP @ 4620' & 2 SX CMT. PLUG AT 1590' WITH 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK BACKSIDE WITH 50 SX CMT TO 300#.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2012 11:25 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4622' WITH 2 SX CMT. 1ST PLUG AT 1594' WITH 50 SX CMT. 2ND PLUG AT 763' WITH 50 SX CMT. 3RD PLUG AT 66' WITH 20 SX CMT. CMT CIRCULATED. CHECKED BACKSIDE TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4670	4672		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

[Signature]
RECEIVED (TECHNICIAN)
AUG 08 2012 8/15/12

RECEIVED
JUL 31 2012
KCC DODGE CITY

KCC WICHITA

[Handwritten mark]