

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22460-00-00
Spot: SWNENE Sec/Twnshp/Rge: 34-13S-20W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: STORM Well #: 6
County: ELLIS Total Vertical Depth: 3839 feet

Operator License No.: 33636
Op Name: TRIUNITED INVESTORS, LLC
Address: 18598 TWIN CREEKS RD
MONTE SERENO, CA 95030

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3839		150 SX
SURF	8.6258	164		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2012 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: JOHN FOSE Company: TRI UNITED INVESTORS LLC Phone: (785) 623-0002

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Casing Leaks @ 1513'-1525'.
Arb-OH from 3839' - 3847'
LKC Perfs: 3739'-3747'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/31/2012 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf tech perforated @ 2050', 1560' and 860'.
Professional Pulling Services ran in hole with tubing to 3613'. Quality rigged to tubing, mixed and pumped 180 sx cement w/300 # hulls.
Pulled tubing to 1997'. Quality rigged to tubing, mixed and pumped 225 sx w/200 # hulls to circulate cement to pit area.
Pulled tubing. Topped off 5 1/2" casing w/60 sx cement. Hole standing full.
Rigged to 8 5/8" casing. Instant pressure. 500 psi.

Perfs:

Top	Bot	Thru	Comments
3839	3847		ARBUCKLE
3739	3747		LKC

Remarks: QUALITY WELL CEMENTING CO. TICKET # 5060

Plugged through: TBG

District: 04

Signed

[Signature]
8/15/12

(RECEIVED)

CM

AUG 08 2012

Form CP-2/3

KCC WICHITA

JUL 31 2012