

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20715-00-00  
Spot: NENWSENW Sec/Twnshp/Rge: 29-15S-21W  
3636 feet from S Section Line, 3390 feet from E Section Line  
Lease Name: UNREIN Well #: 1  
County: TREGO Total Vertical Depth: 4400 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4398		100 SX
SURF	8.625	249		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/02/2012 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE KERNS Company: WHITETAIL CRUDE, INC Phone: (785) 626-3780

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perfs: 4331'-4335' and 4309'-4312'.  
Shot Perfs @ 2250', 1737' and 900'.  
Did not shoot perforations in surface pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/02/2012 8:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4360'. Pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 2860'. Pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1360'. Circulated 190 sx cement.  
Pulled tubing out. Topped off w/45 sx cement. Still not full. Let cement set.  
Tied on to back side. Pumped 70 sx cement. Shut in 100 psi.  
Back at 8:15 pm. Topped off casing w/20 sx cement.

Perfs:

Top	Bot	Thru	Comments
4331	4335		
4309	4312		

RECEIVED  
AUG 13 2012  
KCC WICHITA

Remarks: SWIFT CEMENT CO TICKET # 22793

Plugged through: TBG

District: 04

Signed Marvin Mills  
8/15/12 (TECHNICIAN)

CM

AUG 06 2012