

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21013-00-00
Spot: S2SESW Sec/Twnshp/Rge: 33-31S-39W
330 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SULLIVAN B Well #: 1
County: MORTON Total Vertical Depth: 6000 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5518		
COND	20	30		WITH 10 SX CMT
DVT		3083		WITH 475 SX CMT
PROD	5.5	6000	0	WITH 1100 SX CMT
SURF	8.625	1723		WITH 675 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2012 10:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS ON BOTTOM. PLUG AT 1750' WITH 30 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 30' WITH 5 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 08/01/2012 5:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMP DOWN 5 1/2" CASING WITH 200# HULLS & 25 SX CMT. 1ST PLUG AT 1750' WITH 30 SX CMT. 2ND PLUG AT 550' WITH 35 SX CMT. 3RD PLUG AT 40' WITH 5 SX CMT. PUMPED DOWN 5 1/2" X 8 5/8" ANNULUS WITH 10 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
5520	5524		
5505	5510		

RECEIVED
AUG 13 2012

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED

AUG - 6 2012

KCC DODGE CITY

Signed

Richard W. Lacey
8/15/12

(TECHNICIAN)

RLW