

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21037-00-00  
Spot: S2NESW Sec/Twnshp/Rge: 33-31S-39W  
1653 feet from S Section Line, 3278 feet from E Section Line  
Lease Name: SULLIVAN B Well #: 2  
County: MORTON Total Vertical Depth: 6000 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	32		WITH 4 SX CMT
PROD	5.5	5990	0	WITH 1110 SX CMT
SURF	8.625	1729		WITH 635 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/03/2012 1:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS AT 5508'. PLUG AT 1760' WITH 30 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 40' WITH 5 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/03/2012 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT WITH 200# HULLS TO 5508'. 1ST PLUG AT 1760' WITH 30 SX CMT. 2ND PLUG AT 550' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 5 SX CMT. PUMP 15 SX CMT DOWN ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
5502	5508		

RECEIVED  
AUG 13 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*  
8/15/12  
(TECHNICIAN)

RECEIVED  
AUG - 8 2012  
KCC DODGE CITY

*Rawy*