

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21869-00-00
Spot: E2NENWNW Sec/Twnshp/Rge: 5-33S-39W
330 feet from N Section Line, 1020 feet from W Section Line
Lease Name: HAYWARD FARMS Well #: 5 #1
County: MORTON Total Vertical Depth: 6193 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5820		WITH 5 SX CMT
CIBP		6010		
PROD	4.5	6178	2818	WITH 275 SX CMT
SURF	8.625	1604		WITH 480 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/02/2012 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5821' WITH 5 SX CMT. PLUG AT 1654' WITH 100 SX CMT. PLUG AT 630' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 08/02/2012 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 5820' WITH 5 SX CMT. RUN TBG TO 1652'. 1ST PLUG AT 1652' WITH 100 SX CMT. 2ND PLUG AT 627' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6018	6022		
5871	5980		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
AUG - 8 2012
KCC DODGE CITY

RECEIVED
AUG 13 2012
KCC WICHITA