

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22394-00-00
Spot: NENENESE Sec/Twnshp/Rge: 27-19S-28W
2540 feet from S Section Line, 88 feet from E Section Line
Lease Name: BUSST UNIT Well #: 1-27
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	261		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/05/2012 3:00 PM
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC
Proposal Rcvd. from: LOU TRESNER Company: H. D. DRILLING, LLC Phone: (785) 372-5419

Proposed Plugging Method: 1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE
Date/Time Plugging Completed: 08/05/2012 5:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

Perfs:

1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED
AUG 13 2012
KCC WICHITA

District: 01

RECEIVED
AUG - 8 2012
KCC DODGE CITY

Signed Daniel Bernasconi
(TECHNICIAN)
8/15/12