

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20441-00-00
Spot: SW Sec/Twnshp/Rge: 14-24S-41W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HCU Well #: 1441-C
County: HAMILTON Total Vertical Depth: 2468 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2260		WITH 10 SX CMT
CIBP		2408		
PROD	4.5	2468	0	WITH 750 SX CMT
SURF	8.625	358		WITH 230 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/28/2012 10:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVET Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: CIBP @ 2260' & 2 SX CMT OR SPOT 25 SX CMT & HULLS. PLUG AT 1740' WITH 25 SX CMT. PLUG AT 800' CIRCULATE TO SURFACE. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2012 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2260 WITH 10 SX CMT. 1ST PLUG AT 1740' WITH 25 SX CMT. 2ND PLUG AT 800'-0' WITH 65 SX CMT. PUMP 35 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2312	2330		

RECEIVED
AUG 13 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED CLASS A COMMON CMT BY KIVET PLUGGING.

Plugged through: TBG

District: 01

RECEIVED

JUL 31 2012

KCC DODGE CITY

Signed

Ken Jehlik
8/15/12

(TECHNICIAN)

AWZ