

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20231-00-00
Spot: NESW Sec/Twnshp/Rge: 19-22S-41W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: HCU Well #: 1921-B
County: HAMILTON Total Vertical Depth: 2782 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2782	0	WITH 550 SX CMT
SURF	8.625	264		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/30/2012 9:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: CIBP @ 2650' & 5 SX CMT OR SPOT HULLS & 25 SX CMT. PLUG AT 2240' WITH 25 SX CMT. CIRCULATE CMT FROM 1200' TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/30/2012 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT AT 2665 TO 2000'. (PERFS ARE COVERED WITH FILL UP FROM CASING LEAK) SPOT 100# HULLS IN 5 BBLs GEL WATER AT 1500'. GOOD CIRCULATION. PULL TBG TO 1200' & CIRCULATE CMT TO SURFACE USING 95 SX CMT. PUMP 30 SX CMT DOWN THE ANNULUS TO 100#. TOP OFF 4 1/2" CASING WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2705	2711		

Remarks: USED CLASS A CMT BY EXCEL SERVICES.

Plugged through: TBG

RECEIVED

AUG 13 2012

KCC WICHITA

District: 01

Signed

[Signature]
8/15/12

(TECHNICIAN)

RECEIVED
JUL 31 2012
KCC DODGE CITY

[Handwritten mark]