

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-129-00135-00-01
 Spot: NW Sec/Twnshp/Rge: 2-33S-41W
1320 feet from N Section Line, 1320 feet from W Section Line
 Lease Name: MOORE C Well #: 1-2
 County: MORTON Total Vertical Depth: 5326 feet

Operator License No.: 34545
 Op Name: ELM III OPERATING COMPANY LLC
 Address: PO BOX 2446
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2093		WITH 2 SX CMT
CIBP		2885		
CIBP		3025		
CIBP		3315		
CIBP		5270		
PROD	4.5	5326	0	WITH 700 SX CMT
SURF	8.625	1589		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/01/2012 8:00 AM
 Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
 Proposal Revd. from: KENNY KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 08/01/2012 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2093' WITH 2 SX CMT. (COULD NOT GET DEEPER THAN 2093' WITH SINKER BAR). SHOOT CASING WITH NITRO @ 1625'. SPOT 50 SX CMT AT 1625' WITH FULL RETURNS. SHOOT CASING WITH NITRO AT 600'. CIRCULATE CMT TO SURFACE WITH 185 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5291	5294		
5228	5232		
3173	3238		
2894	2940		
2852	2860		
2817	2829		
2774	2789		
2732	2749		
2635	2642		

Remarks: USED CLASS A COMMON CEMENT BY KIVET PLUGGING.

Plugged through: CSG

RECEIVED
 AUG 13 2012

KCC WICHITA

District: 01

RECEIVED

AUG - 8 2012

KCC DODGE CITY

Signed

[Signature]

(TECHNICIAN)

[Signature]
 8/15/12

[Handwritten mark]