

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20636-00-01
Spot: NWNE Sec/Twnshp/Rge: 2-33S-41W
660 feet from N Section Line, 1980 feet from E Section Line
Lease Name: EAGLEY D Well #: 1
County: MORTON Total Vertical Depth: 3100 feet

Operator License No.: 34545
Op Name: ELM III OPERATING COMPANY LLC
Address: PO BOX 2446
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3077		
PROD	4.5	3096	0	WITH 675 SX CMT
SURF	8.625	637		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/01/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNY KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 08/02/2012 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TIH W/TBG & TAGGED TOP OF FISH @ 240'. RAN SPEAR ON TBG. GOT IN TO 2 1/16" TBG & PULLED 35000#. COULD NOT MOVE FISH. STUCK. PUMPED 200 SX CMT DOWN 4 1/2" CASING @ 0 PSI. SDON. 8/2/12: PUMPED 50 SX CMT DOWN 4 1/2" CASING. LOAD & PRESSURE CASING TO 100#. (TOC FROM 8/1/12 CALCULATES 650' DOWN) HOOK UP TO 4 1/2" X 8 5/8" ANNULUS & PUMP 45 SX CMT. PRESSURE TO 50#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2896	2902		
2857	2902		
2778	2880		
2739	2746		
2696	2710		

Remarks: USED CLASS A COMMON CEMENT BY KIVET PLUGGING.

Plugged through: CSG

District: 01

Signed _____

Ken Jehlik
8/2/12
(TECHNICIAN)

RECEIVED
AUG - 8 2012
KCC DODGE CITY

RECEIVED
AUG 13 2012
KCC WICHITA

RAW