

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23045-00-00
Spot: NENENE Sec/Twnshp/Rge: 15-25S-11W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: CRAVENS Well #: 1-15
County: STAFFORD Total Vertical Depth: 4100 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI
Address: 8100 E 22ND ST N
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2900		
PROD	5.5	4067	2030	WITH 290 SX CMT
SURF	8.625	259		WITH 185 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/03/2012 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIR HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 2775' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 08/02/2012 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUT ADDITIONAL PLUG @ 1150' DUE TO SLIGHT GAS FLOW SANDED TO 2774' & 5 SX CMT WITH A DUMP BAILER. 1ST PLUG AT 1150' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 610' WITH 50 SX CMT. 3RD PLUG AT 305' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3855	3891		
3628	3632		
2823	2826		

RECEIVED
AUG 13 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

Steve Pfeifer
8/16/12 (TECHNICIAN)

RECEIVED
AUG - 6 2012
KCC DODGE CITY

Row Y