

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21435-00-00
Spot: NWSENE Sec/Twnshp/Rge: 23-22S-16W
3779 feet from S Section Line, 998 feet from E Section Line
Lease Name: DRINGMANN Well #: 1-23
County: PAWNEE Total Vertical Depth: 4075 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI
Address: 8100 E 22ND ST N
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2070		
PROD	5.5	4074	0	WITH 412 SX CMT
SURF	8.625	273		WITH 190 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/07/2012 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 1990' & 5 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2012 3:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 1973' & 5 SX CMT WITH DUMP BAILER. 8 5/8" X 5 1/2" ANNULUS FULL OF CMT AT SURFACE. PERFORATED @ 1000' & 290'. RAN TBG TO 1023'. CIRCULATED CMT TO SURFACE WITH 100 SX CMT. PULLED TBG & SWAGED IN CASING. FILLED CASING & PRESSURED 5 1/2" TO 600 PSIG WITH 28 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4022	4030		
3757	3760		
3737	3740		
3712	3715		
3616	3618		
3596	3599		
3129	3134		
2384	2387		
2080	2085		
2038	2045		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

RECEIVED
AUG 13 2012
KCC WICHITA

District: 01

RECEIVED
AUG - 8 2012
KCC DODGE CITY

Signed Richard W. Lacey
8/15/12 (TECHNICIAN)

Randy