

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00177-00-00
Spot: SE Sec/Twnshp/Rge: 11-21S-33W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HIPP Well #: 1-11
County: FINNEY Total Vertical Depth: 2710 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1200		
CIBP		2331		WITH 2 SX CMT
PROD	5.5	2708	0	WITH 300 SX CMT
SURF	8.625	282		WITH 260 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/27/2012 12:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0806

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2012 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2331' WITH 2 SX CMT. CIBP @ 1200'. TEST CASING TO 700#. HOLDING. RUN BOND LOG FROM 1200' TO 0'. TOP OF GOOD CMT FROM PREVIOUS SQUEEZE JOB AT 1274' TO 1306' WITH 300 SX CMT IS 884'. SCATTERED CMT TO 650'. PERFORATE AT 310'. ESTABLISH INJECTION RATE AT 1 1/4 BPM @ 350#. 8/1/12: RUN TBG TO 1200' & CIRCULATE CMT TO 450' WITH 75 SX CMT. FULL CIRCULATION. TOOH W/TBG. CIRCULATE CMT TO SURFACE DOWN 5 1/2" CASING THROUGH PERFS @ 310' WITH 80 SX CMT LEAVING CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2611	2633		
2581	2586		


RECEIVED
AUG 13 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed


8/15/12 (TECHNICIAN)

AWY