

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00218-00-00  
Spot: E2W2W2NE Sec/Twnshp/Rge: 29-33S-39W  
3954 feet from S Section Line, 2203 feet from E Section Line  
Lease Name: FIDLER Well #: 1  
County: MORTON Total Vertical Depth: 2670 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: PO BOX 1330  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1043		WITH 50 SX CMT
PROD	7	2450	0	WITH 800 SX CMT
SURF	10.75	521		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/03/2012 9:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: MIGUEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SANDED TO 1190'. PLUG AT 1190' WITH 25 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/03/2012 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAGGED FILL UP @ 1190'. SET CIBP @ 1043' & SPOT 50 SX CMT ON TOP. PUMP 90 SX CMT FROM 550' TO 0'. FULL CIRCULATION. TOOH W/TBG. TOP OFF WITH 10 SX CMT. 7" X 10 3/4" ANNULUS IS FULL OF CMT TO THE TOP.

Perfs:

Top	Bot	Thru	Comments
2450	2670		

RECEIVED  
AUG 13 2012  
KCC WICHITA

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)  
8/15/12

RECEIVED

AUG - 8 2012

KCC DODGE CITY

*Root*