

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21721-00-00  
Spot: SWNWSENE Sec/Twnshp/Rge: 3-28S-18W  
1708 feet from N Section Line, 1288 feet from E Section Line  
Lease Name: RICHARDSON Well #: 1-3  
County: KIOWA Total Vertical Depth: 4890 feet

Operator License No.: 33036  
Op Name: STRATA EXPLORATION, INC.  
Address: PO BOX 401  
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4180		WITH 2 SX CMT
CIBP		4380		
PROD	5.5	4888	2335	WITH 200 SX CMT
SURF	8.625	622		WITH 350 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/02/2012 8:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: MICHEAL POLLY Company: STRATA EXPLORATION Phone: (719) 846-3434

Proposed Plugging Method: SET CIBP @ 4180' WITH 2 SX CMT. PLUG AT 1170' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/02/2012 11:20 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4180' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1161' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 652' WITH 50 SX CMT. 3RD PLUG AT 316' WITH 40 SX CMT. 4TH PLUG AT 41' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4476	4480		
4451	4456		
4396	4400		
4230	4236		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

RECEIVED  
AUG 13 2012

KCC WICHITA

District: 01

RECEIVED  
AUG - 6 2012  
KCC DODGE CITY

Signed Richard M. Lacey  
8/16/12 (TECHNICIAN)

RAM