

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20827-00-00
Spot: SENENE Sec/Twnshp/Rge: 16-26S-22W
955 feet from N Section Line, 465 feet from E Section Line
Lease Name: HESKAMP 16A Well #: 1
County: FORD Total Vertical Depth: 5020 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	360		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/03/2012 8:45 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 830' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 08/03/2012 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 830' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY.

Plugged through: DP

RECEIVED
AUG 13 2012
KCC WICHITA

District: 01

Signed Steve Pfeifer
(TECHNICIAN)
8/16/12

RECEIVED
AUG - 6 2012
KCC DODGE CITY

AWY