

1 110015

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,344 - 0000
165' E of
NW NE SW, SEC. 29, T 16 S, R 19 WXB

TECHNICIAN'S PLUGGING REPORT

Operator License # 4087

Operator: Williamson Drilling, Inc.
Name & Address
5501 Navajo
Great Bend, KS 67530

2310 feet from S section line

3465 feet from E section line

Lease Name Krug "A" Well # 1

County Rush

Well Total Depth 3900 Arubckle 126.75 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Williamson Drilling, Inc. License Number 4087

Address 5501 Navajo, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 19 Month: December Year: 19 85

Plugging proposal received from Terry Williamson

(company name) Williamson (phone) 316-793-8229

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1355' Elevation 2060'

1st plug in the Arubckle with 50 sx cement if 50' or more

2nd plug at teh base of the Anhydrite with 50 sx cement

3rd plug at 1/2 the Anhydrite with 80 sx cement

4th plug 30' below the base of the surface pipe with 30 sx cement

5th plug 10 sx cement solid bridge - hulls - plug at 40' -- cement to surface with

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:00 pm Day: 19 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3827' with 50 sx cement, 2nd plug at 1357' with 50 sx cement, 3rd plug at 678' with 80 sx cement, 4th plug at 282' with 30 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging

STATE CORPORATION COMMISSION Signed

James R. Kapp (TECHNICIAN)

DATE DEC 27 1985

INV. NO. 11760

DEC 27 1985
12-27-85
CONSERVATION DIVISION

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

2

Starting Date ... December ... 5 ... 1985

API Number 15- 165-21,344-0000
165' E of
NW. NE. SW Sec. 22. Twp. 16 S, Rg. 12 X West
2310 Ft. from South Line of Section
3465 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

OPERATOR: License # 4087
Name Williamson Drilling Inc.
Address 5501 Navajo
City/State/Zip Great Bend, Ks 67530
Contact Person Terry L. Williamson
Phone 316-793-8229

CONTRACTOR: License # Unknown
Name Unknown Co. tools
City/State

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Nearest lease or unit boundary line 330 feet
County Rush
Lease Name Krug "A" Well # 1
Ground surface elevation 2060 EST feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 200'
Depth to bottom of usable water 700'
Surface pipe planned to be set 240'
Projected Total Depth 3900 feet
Formation Arbuckle

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Yes cementing will be done immediately upon setting production casing.
Date 12-2-85 Signature of Operator or Agent Terry L. Williamson Title President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2
This Authorization Expires 6-4-86 Approved By 12-9-85

Pusher Jerry Williamson

Handwritten notes: TD 3906, 248' 8 1/8, 1st 50' out, 2nd 50' out, 3rd 80' out, 4th 30' out, 40' clear 5 1/2" 1 hole 10' out, 10' out, Mud Waste, Halibut Cement 6/4/6 70, actual, TD TD 3900 surface bit 8 1/2" 248, 1st 3827 w/ 50, 2nd 387 w/ 50, 3rd 78 w/ 80, 4th 288 w 30, 5th 40 10 w 10, 10' out, added, 12-19-85 @ 4:00 PM

RECEIVED STATE CORPORATION COMMISSION

DEC 27 1985

CONSERVATION DIVISION Wichita, Kansas